Results for the 8'x200' circular tank with ramp:

Circular tank:

Tank Diameter = 200 ft
Tank Wall thickness = 12 in (actual)
Tank Height = 8 ft
f_y= 60,000 psi
f'_c = 4,000 psi

Horizontal Steel = #4 rebar
Steel shown in table must be placed in each face of the wall

Bar #	Spacing (in)	Distance from finished floor (ft - in)
1	3	0' 3"
2	12	1' 3"
3	12	2' 3"
4	12	3' 3"
5	12	4' 3"
6	12	5' 3"
7	8	5' 11"
8	8	6' 7"
9	8	7' 3"
10	6	7' 9"

Vertical Steel = #4 @ 12" O.C. in each face.
Dowels "L" bars from tank to footing shall be #4 @ 12" O.C. at the interior mat of steel.
26" vertical leg, 6" horizontal leg

In the tank wall, at the corner of the notch for the ramp add:

3-#6 bars x 7'-10" long @ 6" O.C. vertically in each mat of steel (6 total)
3-#6 bars x 20' long @ 6" O.C. horizontally in each mat of steel (6 total)
4-#6 bars x 6 feet long @ 6" O.C. at a 45 degree angle in each mat of steel (8 total).